

URBAN IMPROVEMENT TRUST, BIKANER

NIT NO. :- /I/2019-20

कार्य का नाम :- Nalla covering work near Ganga residency Suraj vihar colony, Bikaner

Estimated Cost :- 31.43 Lacs

Earnest Money :- 2% =Rs. 62860.00 1/2% =Rs. 15715.00

Tender Fee :- 1000/-

Date of Sale :-

Date of Received :-



Date of Opening :-


'G'- SCHEDULE'

Rate Based on BSR 2013 of PWD Circle, Bikaner

S.No.	Item	UNIT	QTY.	RATE	AMOUNT
1	Earth work in excavation by mechanical means (Hydraulic Excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including taking out the excavated soil and depositing and refilling of jhiri with watering & ramming and disposal of surplus excavated soil as directed with in a lead of 50 meter. All kinds of soils	CUM	50	153	7650
2	Silt clearance of drains, channels and canals with lift 1.5 Mtr. and lead up to 50Mtr.	Cum	350	100	35000
	Add extra for foundations /trenches/ drains for every additional lift of 1.5 Mtr. or par thereof All kind of soil.	Cum	350	37	12950
3	Carriage of Earth, Sand, Lime Morrum manure or sludge, U/S Kankar for all lead	Cum	400	70	28000
4	Dismantling old plaster or skirting, raking out joints and cleaning the surface for plaster incl. disposal of rubbish to the dumping ground within 50mtr lead	Sqm	450	16	7200
5	Plaster on new surface on walls in cement sand mortar 1:4 including raking of joints etc. complete fine finished. 20 mm thick.	Sqm	650	164	106600
6	Centering & shuttering with plywood or steel sheets including strutting, propping bracing both ways with steel props and removal of formwork for upto floor five level for : Suspended floors, roofs, landings, staircases, balconies, girders, cantilevers, bands, coping, bed plates, anchor blocks, sills, chhajjas lintel, beam etc.	Sqm	567	269	152523
7	Providing and laying in position specified grade of cement concrete for all RCC structural elements upto plinth level including curing, compaction, finishing with rendering in cement sand mortar 1:3 (1 cement: 3 coarse sand) and making good the joints and cost of plasticizer(if required) excluding the cost of centering, shuttering and reinforcement. M20 grade Nominal Mix/Design Mix	Cum	140	4053	567420
8	Providing and fabricating reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding (including cost of binding wire) all complete up to floor Five level.Cold twisted deformed bars (IS : 1786).	Kg	21750	61	1326750
9	Brick work with F.P.S. bricks of class designation 100 in foundation and plinth in: Cement Mortar 1:6 (1-Cement:6-coarse sand).	CUM	112	3756	420672



10	Providing and laying in position cement concrete including curing compaction etc. of specified grade excluding the cost of centering and shuttering - All up to plinth level M15 grade Nominal Mix 1: 2: 4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size).	Cum	60	3525	211500
11	Providing and laying in position cement concrete including curing compaction etc. of specified grade excluding the cost of centering and shuttering - All up to plinth level 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size).	CUM	15	2761	41415
12	Providing and fixing of Reinforced Ferro cement Drain cover designed for class 'A' & 'AA' loading duly marked on cover with adequate steel reinforcement having thickness 75 mm to 150 mm anti-corrosive bitumen painted M.S. plate Rim and on M.S. lifting hooks admixture like plasticizer bond improving compound shrinkage resistance compound abrasion resistant complete as per approved design etc. SPAN STANDARD SIZE 1201 to 1500 mm 2100x500mm A class loading	Sqm	75	3000	225000
					3142680
  Executive Engineer, U.I.T. Bikaner					
Special Conditions :-					
1	कार्य की दोष निवारण अवधि (Defect Liability Period) का समय 3 वर्ष एवं कम से कम एक बारिश के मौसम के निकलने तक होगा ।				
2	यदि निविदा में प्रस्तुत दर प्रचलित बी.एस.आर. जिस पर निविदा आधारित है से जितनी प्रतिशत कम जाएगी उस में से 10 प्रतिशत घटाकर उतनी राशि की बैंक गारण्टी / डी.डी. विभाग में जमा कराना होगा जिसे वास्तविक कार्य पूर्णता तिथि के 28 दिन बाद कार्य सन्तोषजनक होने पर लौटाई जावेगी । कार्यादेश जारी होने के पश्चात कार्य प्रारम्भ करने की दिनांक से पूर्व ही बैंक गारण्टी / डी.डी. जमा करवाना होगा, अन्यथा अमानत राशि जब्त कर 6 माह के लिये निविदा में भाग लेने से प्रतिबन्धित कर दिया जायेगा ।				
3	कार्य आरम्भ करने के वक्त कार्य स्थल पर 3X3 फीट लोहे के रिफ्लैक्टिव बोर्ड पर कार्य का सम्पूर्ण विवरण लिखकर कार्य साईड पर लगाना होगा। एवं मौका साईट का फोटो लेना होगा। कार्य पूर्ण होने पर संवेदक द्वारा एम.पी/एम.एल.ए के नाम-की मार्बल पत्थर पर गड़ाई करवाकर पत्थर लगवाना होगा एवं मौका साईट का फोटो लेना होगा। जिसका खर्च राशि संवेदक द्वारा व्यय होगी।				
4	For any typographical error, relevant Building BSR 2013, NH-BSR-2013, Road BSR 2013 and UIT approved Electric BSR shall be the binding & final.				
5	Dewatering / Pumping/ Diversion of water / coffer dam etc. if required at ite shall be done by contractor at his own cost.				
6	Contractor shall be liable for any damage of pipe line, sewer line/ cables, OFC etc. during the work.				
7	Safe Diversion arrangement like safety ribbon, safety cone, Diversion Information board and other required shall be done by Contractor on his own cost.				
8	Conditional Tender shall not be acceptable.				
9	Contractor must to be establish lab on site for various tests which is executed on site through out the construction period.				
10	Contractor must to be depute a degree holder engineer on the site for entire construction period.				


Executive Engineer
U.I.T. Bikaner

I/We tendered the rate @ % above/ below of the 'G' – Schedule.

