

OFFICE OF THE URBAN IMPROVEMENT TRUST , CHITTORGARH

G-SCHEDULE

Name of Agency :-

NAME OF WORK :- Const. of C.C. Road from pandoli - paroli road to rolahera road using RMC Plant

Estimated cost : 16.00 lacs

Duration of work : 03 Month

Date of sale of tender : 26.12.2016 to 16.01.2017, 6.00 pm

Earnest Money : 32000 /-

Date of Opening of tender : 18.01.2017, 6.00 pm

DD/bankers cheque No. :

Tender fees : 1000/-

S. NO.	Code No.	Particular	Qunt.	Unit	Rate	Amount
(i)	R-3/8	Construction of embankment with approved Material obtained from borrow-pits with all lift sandleads,transporting to site, spreading,grading to required slope and compacting by vibratory roller 8-10 to n neto meet requirement of Table 300-2 including cost of compensation for earth taken from private land with lead upto 1 km as per MoRTH Specification : Clause No. 305.	1215.00	Cum	98	119070.00
(ii)	R-4/1.1.3	Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401. For Grading III Material	585.00	Cum	417	243945.00
(iii)	R-5/2	Providing, laying, spreading and compacting crushed graded stone aggregate as per Table 400-10 & 400.11 to Wet Mix Macadam specifications including premixing the Material with water to OMC in mechanical mixer (Pug mill) as per design mix, carriage of mixed Material by tipper to site laying in uniform layers, with motor grader/F.E. loader/Paver Finisher, in sub-base/base course on a well prepared under-base and compacting with Vibratory Roller to achieve the desired density including lighting, guarding, barricading and maintenance of Driversion etc. (MoRTH specification : Clause 406). with all lead & lift	150.00	Cum	1050	157500.00

(iv) R-7/3.3	Construction of un-reinforced, dowel jointed at expansion and construction joint only, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed, plate vibrators and vaccum process and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs for 14-days	300.00	Cum	5024	1507200.00
Grant Total					2027715.00

**EXECUTIVE ENGINEER
UIT CHITTORGARH**

I/we agree to execute the work

(in figure)% above/below

(in word)% above/below

I/we shall abide to the important terms and conditions as per UIT office order No.

**Signature of contractor
With full Address**